

City of Longview Bid Register

Bid Project: REMOVE & REMOUNT 5 YARD DUMP BOX

Bid Opening Date/Time: TUESDAY, JULY 12, 2016 / 10:00 AM

Vendor	Received		Received by - delivered/init.	Bid \$\$ Amount
	Date	Time		
RANDCO TANKS	6/30	11:37A	hand-del/CMM	23,328.00

Signature of person receiving bids
from Executive Office:

Kaylee Cady

Date/Time Bids picked up:

7/12/16

BID PROPOSAL/SIGNATURE SHEET

THE UNDERSIGNED PROPOSES TO BID THE FOLLOWING:

REMOVE AND REMOUNT 5 YARD DUMP BOX:

Base Bid, less Federal Excise and State Sales Tax:

\$ 21,600.00

Any applicable taxes at 8 % Type SALES
(Specify percent and type of tax)

\$ 1,728.00

Total Bid:

\$ 23,328.00

Firm **Delivery Date**, F.O.B. City Longview Fleet Services
254 Oregon Way, Longview, Washington
\$150 per day penalty fee for late delivery.

Date: OCTOBER 7, 2016

Supplier:

RANDCO TANKS INC.
Company Name

By:

RANDY SALVIG PRESIDENT
Authorized Official Title

JUNE 30, 2016
Date

Signature

Address:

2250 TALLEY WAY
KELSO, WA 98026

Email Address:

sales@randcotanks.com

Phone:

(360) 425-9100

Fax: (360) 425-5570

ADDENDA:

Receipt of Addenda No. _____ is hereby acknowledged. (If applicable)

Signature

Date

State of Washington License Numbers: 602-179-345

Vehicle Dealer's License: 7224

Tax Registration: 01-0614970

If supplier is a corporation, this proposal must be executed by its duly authorized officials.

SPECIFICATIONS CONTINUED **REMOVAL AND REMOUNT 5 YARD DUMP BOX**

SUPPLIER SHALL COMPLETE BY CHECKING THE FOLLOWING.
 IF NOT COMPLIANT, STATE SPECIFICALLY THE ITEM BEING OFFERED.

THE FOLLOWING DETAILED SPECIFICATIONS ARE ***MINIMUM REQUIREMENTS***:

BASIC EQUIPMENT INCLUDED IN NET PRICE

A. GENERAL		YES	NO	OFFERED
1.	Remove and remount City owned 5 yard dump box on City furnished chassis, relocate flow control and pump controls to center console utilizing customers hydraulic components.	(X)	()	_____
2.	Hydraulic Flange Hot Shift PTO Upgrade Installed	(X)	()	_____
3.	Fabricate and install new rear hitch plate w/hydraulic connections to sander, air gland hands and electrical trailer connection. (City will provide hitch).	(X)	()	_____
4.	Convert 5 yard dump box tailgate to high lift gate.	(X)	()	_____
5.	Install left and right side asphalt gates into tailgate (pull half round style).	(X)	()	_____
6.	Fabricate and install front bracket for plow using existing truck as an example.	(X)	()	_____
7.	Mount passenger side ladder onto dump box.	(X)	()	_____
8.	Sandblast dump box.	(X)	()	_____
9.	Chassis black touch up.	(X)	()	_____
10.	Paint 5 yard dump box to match chassis cab color.	(X)	()	_____
B. CITY FURNISHED CHASSIS				
1.	2016 Freightliner M108SD Chassis	(X)	()	_____